

3.5"

5.5"



# Suspend<sup>®</sup>

SC

## INSECTICIDE

- \* For Residential, Industrial and Institutional Control of Major Nuisance Pests Listed on The Label
- \* Controls Numerous Pests in and around Households and Other Structures
- \* Will not Damage Paints, Plastics, Fabrics or Other Surfaces Where Water Alone Causes No Damage
- \* For Insect Control on Commercial and Residential Turf and Landscape Ornamental Plants

**ACTIVE INGREDIENTS:**

\*Deltamethrin .....4.75%

**OTHER INGREDIENTS:**.....95.25%

**TOTAL:** .....100.00%

\*Contains 0.42 lb deltamethrin per gallon.

EPA Reg No. 432-763

### KEEP OUT OF REACH OF CHILDREN CAUTION

Si usted no entiende la etiqueta, busque a alguien para que se la explique a usted en detalle.

(If you do not understand the label, find someone to explain it to you in detail.)

#### FIRST AID

<b>If inhaled:</b>	<ul style="list-style-type: none"> <li>• Move person to fresh air.</li> <li>• If person is not breathing, call 911 or an ambulance, then give artificial respiration, preferably by mouth-to-mouth, if possible.</li> <li>• Call a poison control center or doctor for further treatment advice.</li> </ul>
--------------------	---

#### HOT LINE NUMBER

Have the product container or label with you when calling a poison control center or doctor or going for treatment. You may also contact 1-800-334-7577 for emergency medical treatment.

See Panel for First Aid Instructions and Booklet for Complete Precautionary Statements and Directions for Use.

### Net Contents 1 Gallon

85750720

85827804B 170421AV2

3.5"

5.5"

### PRECAUTIONARY STATEMENTS

#### HAZARDS TO HUMANS AND DOMESTIC ANIMALS

##### CAUTION

Harmful if inhaled. Avoid breathing vapor or spray mist. Contact with product may result in transient tingling and reddening of the skin. Remove contaminated clothing and wash before reuse.

##### ENVIRONMENTAL HAZARDS

This product is extremely toxic to fresh water and estuarine fish and invertebrates. Use with care when applying in areas adjacent to any body of water. To protect the environment, do not allow pesticide to enter or run off into storm drains, drainage ditches, gutters, or surface waters. Applying this product in calm weather when rain is not predicted for the next 24 hours will help to ensure that wind or rain does not blow or wash pesticide off the treatment area. Rinsing application equipment over the treated area will help avoid run off to water bodies or drainage systems.

This pesticide is highly toxic to bees exposed to direct treatment. Do not apply or allow it to drift to crops or weeds on which bees are actively foraging.

##### PHYSICAL & CHEMICAL HAZARDS

Do not use water-based sprays of Suspend SC Insecticide in conduits, motor housings, junction boxes, switch boxes, or other electrical equipment because of possible shock hazard.

<b>Product Facts:</b> <ul style="list-style-type: none"> <li>• Quick Knockdown &amp; Residual Control</li> <li>• Low Odor</li> <li>• Non-staining</li> <li>• No phytotoxicity on wide range ornamentals</li> </ul>	
<b>Suspend SC Insecticide</b>	This product is a suspension concentrate formulation containing 0.42 lb of Deltamethrin per gal. This product is designed for use both indoors and outdoors and will provide effective knockdown and long residual control of the pests listed on this label. For residential, industrial and institutional control of major nuisance and public health pests listed on the label. Will not damage paints, plastics, fabrics or other surfaces where water alone causes no damage.
<b>Controls</b>	<ul style="list-style-type: none"> <li>• Indoor, General Household Pests, Pantry and Stored Product Pests, and Food/Feed Processing/Handling Pests</li> <li>• Outdoor/ Perimeter Pests</li> <li>• Wood-Infesting Pests</li> </ul> For list of specific insects, see inside
<b>Where to Apply</b>	<ul style="list-style-type: none"> <li>• Apply where pests have been seen or found, or can find shelter</li> <li>• In and around buildings and structures</li> <li>• On ornamentals in landscapes and interior plantscapes</li> <li>• On residential, commercial, and recreational areas of turf</li> </ul>
<b>Dilution Rates</b>	<ol style="list-style-type: none"> <li>1. When 1.5 fl oz (45.4 ml) is diluted in one gal of water, the active ingredient concentration is equivalent to 0.06% Deltamethrin. Use of the 1.5 fl oz (0.06%) rate is recommended for severe pest infestations or when longer residual control is desired.</li> <li>2. When 0.75 fl oz (22.7 ml) is diluted in one gal of water, the active ingredient concentration is equivalent to 0.03% Deltamethrin. Use of the 0.75 fl oz (0.03%) rate is recommended for initial service or clean out treatments.</li> <li>3. When 0.25 fl oz (7.5 ml) is diluted in one gal of water, the active ingredient concentration is equivalent to 0.01% Deltamethrin. Use of the 0.25 fl oz (0.01%) rate is recommended for maintenance treatments.</li> </ol>

*continued*

← 3.5" →

5.5"

*continued*

<b>Mixing Information</b>	This product is intended to be mixed with water and applied with hand pressurized or power operated sprayers. Shake this product well before measuring concentrate for dilution in water. Mix the appropriate amount of this product with water. Thoroughly shake, agitate, or invert sprayer to insure proper suspension. If spraying is interrupted when using a back-pack or hand-held sprayer, invert sprayer to re-suspend the dilution before starting to make applications. Diluted spray mixture can be stored overnight, but agitate well before using. If spray screens are used, they should be 50 mesh or larger.
<b>Tank mixing</b>	This product may be tank-mixed with other registered pesticides unless expressly prohibited by the product label. A small volume mixing test with other products is recommended to ensure compatibility. Observe all restrictions and precautions which appear on the labels of these products.
<b>How to Apply</b>	General surface applications, spot treatments, crack and crevice sprays, or void injections by sprays, mists, or foams. Broadcast application to turf and foliar application to ornamentals.
<b>Re-Apply</b>	Treatments may be applied at 21-day intervals, or as necessary to maintain adequate control.
<b>Re-Entry</b>	Avoid contact with treated surfaces until dry. People and pets may re-enter after the treated area is dry.
<b>Questions</b>	For questions or comments, call toll free 1 800 331-2867

**DIRECTIONS FOR USE**


**It is a violation of Federal Law to use this product in a manner inconsistent with its labeling.** Not for use on turf being grown for sale or other commercial use as sod, or for commercial seed production, or for research purposes.


**INDOOR PESTS**

Indoor applications to buildings and structures may be made as a general surface, spot treatment, crack and crevice applications, or void (spray, mist, foam) injections. This includes schools, factories, stores, warehouses, hospitals, food processing facilities (food/feed and non food/feed areas), and modes of transportation. For a list of common facilities where this product may be used, see Appendix.

Ants Bed bugs Bird mites Blue/green bottle flies Boxelder bugs Carpet beetles Centipedes Clothes moths Clover mites Cluster flies Cockroaches Crickets Darkling beetles Dermestids Earwigs Elm leaf beetles Firebrats Fleas	Flesh flies Flies Fruit flies Gnats Hide beetles Hornets House flies Leather beetles Midges Millipedes Moths Multi-colored Asian lady beetles Phorid flies Pillbugs Sciarid flies (fungus gnats) Scorpions Silverfish	Sowbugs Spiders Ticks Wasps Yellowjackets	<u>Pantry and Stored Product Pests: beetles &amp; moths</u> Angoumois grain moths Cigarette beetles Drugstore beetles Flour beetles Foreign grain beetles Grain mites Grain weevils Hairy fungus beetles Indian meal moths Lesser grain borers Mediterranean flour moths Merchant grain beetles Saw-toothed grain beetles Spider mites Warehouse beetles
--	---	---	---


*continued*






<b>APPLICATION FOR INDOOR PESTS</b>	
Ants, Centipedes, Clothes Moths, Cockroaches, Crickets, Earwigs, Firebrats, Millipedes, Pillbugs, Scorpions, Silverfish, Sowbugs, and Spiders	Apply as a coarse, low pressure (do not exceed 50 psi at nozzle tip) spot or crack and crevice spray to areas that these pests normally inhabit. Pay particular attention to dark corners of rooms and closets; floor drains; cracks and crevices in walls; along and behind baseboards; beneath and behind sinks, stoves, refrigerators, and cabinets; around plumbing and other utility installations; doors, window frames and in attics and crawl spaces. Spot applications may be made to floor surfaces along baseboards and around air ducts. Let surfaces dry before allowing people or pets to contact surfaces.
Pantry Pest Control	To kill adult and accessible immature stages of insects such as lesser grain borers, grain weevils, flour beetles, saw-toothed grain beetles, cigarette beetles, merchant grain beetles, Angoumois grain moths, Mediterranean flour moths, Indian meal moths, grain mites and spider mites. Make applications to cupboards, shelving and storage areas. Remove all foodstuffs, all utensils, shelf paper, and other objects before spraying. Allow all treated surfaces to dry before replacing foodstuffs, utensils or other items. Any foodstuff accidentally contaminated with any spray solution must be discarded.
Ants, Cockroaches, Crawling and Flying Insect Pests, Flies, Gnats, Midges, Mosquitoes, and Silverfish	Apply directly to walls, ceilings, window screens and other resting areas as a residual surface treatment. May be used inside residential buildings, as well as in and around carpports, garages, storage sheds, unoccupied barns, stables, or pet kennels.
Ants Including Pharaoh's ant	Apply to trails, around doors and window frames and other areas where ants inhabit or enter premises.
Bed Bugs	Spray bed bugs and eggs directly wherever possible following site directions below. For infested mattresses, remove linens and wash before reuse. Apply to mattresses, especially tufts, folds, and edges until moist. Allow to dry before remaking bed. Apply to bedsprings, box springs, and the interior of bed frames or headboards, including all cracks and crevices. When bed bugs are found in upholstered furniture, apply only to the infested tufts, seams, folds and edges, but do not make broadcast applications to flat surfaces where prolonged human contact will occur. If bugs heavily infest furniture (inside cushions and/or batting) apply a labeled insecticide dust or consider fumigation. Apply as a crack and crevice treatment to all baseboards, moldings, beneath floor coverings and carpets, closets, shelves, curtains, furniture and picture frames that may provide harborage to bed bugs.
Carpet Beetles, Fleas, and Ticks	A total integrated pest management program is recommended. It is suggested that infested areas be thoroughly vacuumed prior to treatment. These areas include all carpet, upholstered furniture, baseboards, and other indoor areas frequented by pets. The vacuum cleaner bag should be discarded in an outdoor trash container upon completion. Pet bedding should be cleaned or replaced. Apply this product as a uniform, coarse low-pressure (do not exceed 50 psi at nozzle tip) spot or crack and crevice treatment to areas where these pests normally inhabit. Care should be taken to limit spot treatments to pet bedding and its surrounding area, infested floor coverings and pest habitats. DO NOT treat entire area of floor, carpet or floor coverings. When these pests are found in upholstered furniture, apply only to the infested tufts, seams, folds and edges, but do not make broadcast applications to flat surfaces where prolonged human contact will occur. This product can also be applied out-of-doors for flea and tick control (see directions in Outdoor/Perimeter Pests).

*continued*



APPLICATION FOR INDOOR PESTS (continued)	
Pet Kennels	For residual control of crawling and flying insects in and around these structures, apply as a general surface and/or crack and crevice spray. Optimal control results if facilities to be treated are clean and if the exterior perimeter is concurrently treated with this product. Apply only to areas of facility where animals are not present. Allow spray to dry before allowing re-entry of animals into treated areas. Do not apply to animal feed or watering equipment. Do NOT treat pets with this product.
Food/Feed Handling Establishments	For control of all labeled pests, applications are permitted in food/feed and non-food/non-feed areas of food/feed handling and processing establishments as a general surface, spot or crack and crevice treatment. Food/Feed handling establishments are defined as places other than private residences in which exposed food/feed is held, processed, prepared or served. Included also are areas for receiving, storing, packing (canning, bottling, wrapping, boxing), preparing, edible waste storage and enclosed processing systems (mills, dairies, edible oils, syrups) of food/feed. Serving areas where food/feed is exposed and the facility is in operation are also considered food/feed areas. Non-Food/Non-Feed Areas: Examples of non-food/non-feed areas include garbage rooms, lavatories, floor drains (to sewers), entries and vestibules, offices, locker rooms, machine rooms, boiler rooms, mop closets and storage (after packaging, canning or bottling). All areas that insects inhabit or through which insects may enter should be treated. General Surface Applications: Do not use this application method in the food/feed handling areas of the facility when the facility is in operation or foods/feeds are exposed. Do not apply directly to food/feed products. Cover or remove all food/feed processing and/or handling equipment during application. After application in food/feed processing plants, cafeterias and similar facilities, wash all equipment, benches, shelving, and other food contact surfaces. Clean exposed food/feed handling or processing equipment and thoroughly rinse with clean, fresh water. After application in bakeries, clean all food contact surfaces thoroughly with appropriate equipment. Spot or Crack & Crevice Applications: Except in federally inspected meat and poultry plants, spot or crack and crevice applications may be made while the facility is in operation provided exposed food is covered or removed from area being treated prior to application. Do not apply directly to food or food-handling surfaces.
Commercial Stored Product Pest	Dilute 0.25-1.5 fl oz of product with water to make 1 gal of solution. Apply finished spray to equipment, wall and floor surfaces of grain bins, warehouses, production facilities, storage areas, rail cars, truck beds, and other areas where products are stored at the rate of 1 gal per 1000 sq ft prior to storing or handling grain. Application should be made only after equipment bins and buildings have been thoroughly cleaned. To help prevent infestation of these structures, apply product as a perimeter treatment where pests are active and may find entrance. It is recommended to treat a band of soil or lawn up to 6-10 feet wide around and adjacent to structures and treat the foundation to a height of 2 to 3 feet. Mix 0.25 - 1.5 fl oz of product with water to make 1 gal of solution. Apply as a coarse spray at a rate of 1 gal per 1000 sq ft. Thoroughly and uniformly wet the barrier area but do not allow run-off to occur.
Stored Grain (Applications to Stored grain not approved for use in the state of California)	Pest Control: To control adults and accessible stages of insect pests such as, <b>lesser grain borer, larger grain borer, Angoumois grain moth, Indianmeal moth, tobacco moth, dermestids, and bean weevil</b> , also to suppress populations of granary weevil, rice weevil, maize weevil, saw-toothed grain beetle, red flour beetle, and confused flour beetle. <b>GENERAL DIRECTIONS FOR TREATMENT</b> Dilute Suspend SC insecticide with water or FDA approved food grade mineral or soybean oils and apply to the moving grain stream as a coarse spray to provide a concentration of 0.5 ppm of deltamethrin on the grain. Final spray volume with water solutions-5 gallons of liquid per 1,000 bushels of grain. Final spray volume with oil solutions should be applied at oil manufacturer's rates. Occasional agitation is needed in water solutions and constant agitation is necessary in oil solutions. A uniform treatment can only be ob-

continued



**APPLICATION FOR INDOOR PESTS** *(continued)*

Stored Grain  
(Applications to  
Stored grain  
not approved  
for use in the  
state of Califor-  
nia)

tained by treating a moving grain stream. Suspend SC Insecticide is to be applied to stored grain in accordance with the General Directions at the rate of 5 gallons of solution per 1,000 bushels to achieve a 0.5 ppm concentration of deltamethrin. Apply at rates as shown in the tables below:


AMOUNT OF SUSPEND SC INSECTICIDE/1,000 BUSHELS OF GRAIN			
GRAIN	SUSPEND SC INSECTICIDE AT 0.5 PPM TREATMENT		GALLONS OF DILUTE
	fl oz	mL	
BARLEY	7.31	216	5
CORN	8.53	252	5
OATS	4.88	144	5
POPCORN	8.53	252	5
RICE	6.86	202	5
RYE	8.53	252	5
SORGHUM (milo)	8.53	252	5
WHEAT	9.14	270	5

Suspend SC Insecticide is to be applied in solution in accordance with the General Directions to stored grains. Final spray volumes to treat 100 metric tons of grain at 0.5 ppm concentrations of deltamethrin are provided in the tables below corresponding to the grain being treated.

AMOUNT OF SUSPEND SC INSECTICIDE/100 METRIC TONS OF GRAIN			
GRAIN	SUSPEND SC INSECTICIDE PER 100 METRIC TONS AT 0.5 PPM		LITERS OF DILUTE SOLUTION
	fl oz	mL	
BARLEY	33.6	993	86.9
CORN	33.6	993	74.5
OATS	33.6	993	130.4
POPCORN	33.6	993	74.5
RICE	33.6	993	92.7
RYE	33.6	993	74.5
SORGHUM (milo)	33.6	993	74.5
WHEAT	33.6	993	69.5

**SEED TREATMENT:** For protection of stored grain seed against injury from stored grain insects listed above. For optimum results, thoroughly clean and treat seed storage areas prior to storage. If seed is insect infested, fumigate\*\* to control existing populations and apply Suspend SC Insecticide for residual protection. Suspend SC Insecticide may also be used in conjunction with registered fungicide or other insecticide seed protectants, to protect barley, corn, oats, popcorn, rice, rye, sorghum and wheat seed during the seed treating process, and prior to bagging or placing in bulk seed storage at the rate of 0.5 ppm. Treated seed with other pesticide products should be properly tagged, indicating the seed should not be used for food, feed or oil purposes. Seed treated with Suspend SC Insecticide alone is considered grain.


\*\*Fumigate with EPA-registered fumigant according to manufacturer's label recommendations



<b>OUTDOOR/PERIMETER PESTS</b>			
Use this product to control outdoor pests by application as a perimeter treatment, residual spray or broadcast application to exterior surfaces of buildings, lawns, grounds, and ornamental plantings.			
Ants Blue or green bottle flies Boxelder bugs Brown marmorated stink bug Carpenter ants Centipedes Cockroaches Cluster flies Clover mites	Crickets Earwigs Elm leaf beetles Fire ants Firebrats Fleas Flesh flies Flies Gnats Ground beetles	Hornets House flies Midges Millipedes Mosquitoes Moths Multi-colored Asian lady beetle Pill bugs Scorpions	Silverfish Sow bugs Spiders Springtails Stable flies Ticks Wasps Yellow jackets
<b>Where to Apply</b>	This product may be applied as a residual spray or as a perimeter treatment around residential and non-residential settings. <b>Residual Spray:</b> Apply to surfaces on building exteriors, porches, patios and other structures, around door and window frames, eaves and attic vents, utility entry points, soffit areas and other exterior openings (including foundation cracks or drilled holes) where pests enter the structure or where they have been seen or found, or can find shelter. <b>Perimeter Treatments:</b> Treat the outside of the structure, including walls (to a height of 2 to 3 feet), around door and window frames, and soffits where pests are active or may enter or hide. Treat the soil, turf, or other ground covering adjacent to the structure (in a band up to 10 feet wide) where pests are seen, have been found, or can find shelter. In ant management programs, apply to flower, shrub or ornamental plant beds where ants may be nesting, find food or forage.		
<b>Application Restrictions</b>	Do not water the treated area to the point of run-off Do not make applications during rain. Do not apply directly to impervious horizontal surfaces such as sidewalks, driveways, and patios except as a spot or crack and crevice treatment. During application, do not allow pesticide to enter or run off into storm drains, drainage ditches, gutters, or surface waters. All outdoor applications, if permitted elsewhere on this label, must be limited to spot or crack and crevice treatments only, except for the following permitted uses: 1. Applications to soil or vegetation, as listed on this label, around structures; 2. Applications to lawns, turf, and other vegetation, as listed on this label; 3. Applications to the side of a building, up to a maximum height of 3 feet above grade; 4. Applications to underside of eaves, soffits, doors, or windows permanently protected from rainfall by a covering, overhang, awning, or other structure; 5. Applications around potential pest entry points into buildings, when limited to a surface band not to exceed one inch in width; 6. Applications made through the use of a coarse, low pressure spray to only those portions of surfaces that are directly above bare soil, lawn, turf, mulch or other vegetation, as listed on this label, and not over an impervious surface, drainage or other condition that could result in runoff into storm drains, drainage ditches, gutters, or surface waters, in order to control occasional invaders or aggregating pests. Application is prohibited directly into sewers or drains, or to any area like a gutter where drainage to sewers, storm drains, water bodies, or aquatic habitat can occur. Do not allow the product to enter any drain during or after application.		


*continued*





<b>OUTDOOR/PERIMETER PESTS</b> <i>(continued)</i>			
<b>Use Rate</b>	0.25 fl oz (7.5 ml) per 1,000 sq ft of surface 0.75 fl oz (22.7 ml) per 1,000 sq ft of surface 1.50 fl oz (45.4 ml) per 1,000 sq ft of surface		
<b>How to Apply (see Application for Outdoor/ Perimeter Pests)</b>	Apply as a coarse low pressure (do not exceed 50 psi at nozzle tip) spray at the rate of 0.25 to 1.5 fl oz of this product per 1,000 sq ft of surfaces. Apply in a sufficient volume of water to provide adequate coverage but do not allow run-off to occur. <b>High volume applications using power sprayers:</b> You must adjust the rate of product dilution to ensure the correct amount of the product (see Use Rate section above) is applied per 1,000 sq ft of treated surface. For example, mixing 12.5 fl oz of this product in a 50 gal tank, while using an application volume of 3.0 gals per 1,000 sq ft, will apply 0.75 fl oz of this product per 1,000 sq ft. The table below gives examples of end use dilutions for typical power spraying application volumes.		
	<b>DILUTION RATE CHART</b> Amount of Product fluid ounces (milliliter)	<b>Application Volume</b> gallons water	<b>Concentration (% AI)</b> in spray solution
	0.25 (7.5)	1	0.01%
		2	0.005%
		3	0.0033%
		4	0.0025%
		5	0.002%
	0.75 (22.7)	1	0.03%
		2	0.015%
		3	0.01%
		4	0.0075%
		5	0.006%
	1.5 (45.4)	1	0.06%
		2	0.03%
		3	0.02%
		4	0.015%
		5	0.012%
<b>When to Apply</b>	Begin applications when pests are noticed. Treatments may be applied at 21-day intervals or as necessary to maintain adequate control.		


<b>APPLICATION FOR OUTDOOR/PERIMETER PESTS</b>	
Ants, roaches, and other listed crawling pests	Apply as a residual spray and/or perimeter treatment around the infested structure as described above. Locate and treat ant nests if possible. Follow trails of foraging worker ants and inspect for likely nest sites. If ants are nesting in soil, drench or inject the nest and surrounding soil. Foliar applications to landscape ornamentals will control aphids, scale insects, and other plant-sucking insects and limit the production of honeydew (an important food source for ant populations). Apply a light mist of the dilute spray, and do not allow excess run-off. Treat thoroughly for good coverage, including the underside of leaves. It is recommended to remove or prune away any shrubbery, bushes, or tree branches touching the structure. Vegetation touching the structure may offer a route of entry for ants into the structure, allowing ants to avoid contact with the treatment.



<b>APPLICATION FOR OUTDOOR/PERIMETER PESTS</b> <i>(continued)</i>	
Occasional invaders including multi-colored Asian lady beetle, boxelder bug, brown mar-marinated stink bug, and elm leaf beetle.	Apply directly to insects that have congregated around doors, window frames, and similar areas where they may enter the structure. Apply a perimeter treatment as described above. For best results, treat trees and shrubs infested with boxelder bugs, elm leaf beetles, and other occasional invading species early in the season. Tree spraying may require ornamental license - check with your local regulator.
Fleas and Ticks (including ticks that may transmit Rocky Mountain Spotted Fever)	Apply as a coarse wet spray to areas where fleas and ticks are most likely to be found, such as dog houses, kennels, runways, along paths or trails, under plants, shrubs, bushes, trees, or other shaded, moist areas where pests may be found. Treat the entire area where these pests could be present. Fleas and ticks may be re-introduced from surrounding areas by host animals.
Mosquitoes (including mosquitoes that may transmit Zika, Dengue, Chikungunya, and West Nile virus)	Treat with spray or mist around landscape plants, turf and ground cover, under decks, around building foundations and other places where mosquitoes may rest.
Fire Ants	Apply as a mound drench. Dilute 1.5 oz per one gal of water. Gently sprinkle 1 to 2 gals of the diluted insecticide over the surface of each mound and surrounding area to a 2-foot diameter. For best results, apply in cool weather, 65 to 80°F or in early morning or late evening hours. Treat new mounds as they appear.
Scorpions	Treat areas where scorpions may hide. Treat known or suspected harborages on and around exterior walls. Apply spot treatments into cracks, crevices, weep holes or other access points into hollow block walls or masonry veneer. Spray around and beneath stones and along rocky areas. Scorpions will often harbor beneath the bark on trees, so inspect these areas and treat as required. When possible, remove piles of debris and building materials near the exterior wall that can harbor the pests. Apply a perimeter treatment to the exterior walls and adjacent soil. You may treat around piles of firewood, but do not treat firewood with this product.
Centipedes, millipedes, pill bugs, sow bugs, springtails.	Apply perimeter treatment to reduce the number of insects entering the structure. Thoroughly treat mulched areas. Correcting moisture problems around the structure will reduce pest pressure.
House flies and Cluster flies	Apply low pressure (do not exceed 50 psi at nozzle tip) mist or spray to outside of surfaces of buildings, porches, patios, garages, fences, and other areas where house flies rest. Cluster flies: Treat in late summer or fall, just before cluster flies begin looking for winter shelter. Spray siding, eaves, around window frames and doors, and window screens. To help reduce infestations, treat cracks and crevices, attics and other indoor winter hiding places.

<b>WOOD-INFESTING PESTS</b>			
Drywood termites Beetles - Lyctid or powder post - Anobiid or deathwatch	Beetles (con't) - False powderpost - old house borers - wharf borers	Beetles (con't) - Ambrosia beetles - bark beetles	Carpenter ants Carpenter bees


*continued*



<b>WOOD-INFESTING PESTS</b> <i>(continued)</i>	
<b>Where to Apply</b>	For treatment of wood infested with, or subject to infestation by, wood-infesting pests. Apply where pests have been seen or found, or can find shelter. Not for structural protection.
<b>Use Rate</b>	0.06% -- 1.50 fl oz (45.4 ml) per gals
<b>How to Apply</b>	Apply spray, mist, or foam as described below in the application section. Treatment dilutions may also be applied to wood surfaces by paint brush or roller. Do not contact treated surfaces until dry.
<b>When to Apply</b>	When pests are seen or found. Treatments may be applied at 21-day intervals, or as necessary to maintain adequate control.
<b>Foam Applications</b>	This product can be converted to foam and used to treat structural voids to control wood-infesting pests in walls, under slabs, within masonry voids, or in other void areas. Mix end-use dilution with manufacturer's specified volume of foaming agent.


**APPLICATION FOR WOOD-INFESTING PESTS**

Drywood termites & wood-in-festing beetles (Not for Structural Protection)	<p><b>Galleries and structural voids:</b> Treat by applying sprays, mists, or foams. Locate galleries by using visual signs (frass or pellets, blistered wood, emergence or clean out holes), the presence of live insects, mechanical sounding techniques, or listening devices (e.g., stethoscopes, acoustic emission detectors). Penetrate the gallery system by drilling holes to receive the injector tip or treatment tool. Distribute drill holes to adequately cover the gallery system. Apply as low pressure (do not exceed 50 psi at nozzle tip) spray, or by misting or, where appropriate, by foaming. Do not treat to the point where runoff is detected from adjacent holes.</p> <ul style="list-style-type: none"> <li>• Avoid drilling where electrical wiring, plumbing lines, etc. are located.</li> <li>• Do not apply where electrical shock hazards exist.</li> <li>• Drill holes in commonly occupied areas must be sealed after treatment.</li> </ul> <p><b>Wood surfaces:</b> Treat by spray or mist or, where appropriate, foam applications. For inaccessible surfaces, drill and treat the interior of structural voids. Surfaces treated may include exposed wooden surfaces in crawlspaces, basements, or attics. Wooden exterior surfaces such as decks, fencing, or siding, structural voids, channels in damaged wood, in spaces between wooden members of a structure, and junctions between wood and foundations. Apply by brushing or as a coarse, low pressure (do not exceed 50 psi at nozzle tip) spray to the wood surface; apply sufficient volume to cover the surface to the point of wetness, but avoid applying to the point of runoff. When spraying wood surfaces overhead in living areas, cover surfaces below the treated area with plastic sheeting or similar material. Do not contact treated surfaces until spray deposits have dried.</p>
Carpenter ants	<p><b>Homes and other structures:</b> Apply around doors and window frames and other places where carpenter ants may enter. Spray or foam into cracks and crevices, or spray, mist or foam through small drilled holes into voids where ants or their nests are present. Use enough spray or foam to cover the area, but do not exceed 1 gal of dilute suspension per 1,000 sq ft of treated surface. It is recommended to remove or prune away any shrubbery, bushes, or tree branches touching the structure. Vegetation touching the structure may offer a route of entry for ants into the structure, allowing ants to avoid contact with the treatment.</p> <p><b>Exterior ant nests:</b> Inside trees, utility poles, fencing and decking materials and similar structural members, drill to find the interior infested cavity and inject spray, mist, or foam using a treatment tool with a backslash guard.</p> <p><b>Tunneling in soil:</b> Apply as a soil drench or inject the dilution or foam in the soil at intervals of 8 to 12 inches. Use 1 gal of dilution per 8 sq ft. Treat along the edges of walls, driveways or other hard surfaces where ants are tunneling beneath the surface.</p> <p><b>Protecting firewood from carpenter ants:</b> Treat soil beneath firewood before stacking at 1 gal of dilution per 8 sq ft. Do not treat firewood with this product.</p>



APPLICATION FOR WOOD-INFESTING PESTS (continued)	
Carpenter bees	Apply as a spray or mist, or sufficient volume of foam, directly into gallery entrance holes. Leave entrance open to be sure that returning adult bees are killed. When there is no longer any insect activity, the entrance hole may be sealed with a suitable sealant. Exterior wood surfaces may be treated by general surface application to prevent nest cavity excavation by adult carpenter bees.

<b>Turfgrass Applications</b>	Suspend SC Insecticide controls a broad spectrum of insects on turfgrasses and ornamental plants in outdoor areas such as athletic fields, recreational areas, residential landscapes, parks, and public and commercial sites such as around institutional commercial and industrial buildings.		
	Uniform coverage is essential. Begin applications when pests are evident. Apply Suspend SC Insecticide as a broadcast application using a conventional hydraulic boom-type sprayer or other suitable equipment for turfgrass pests according to the rates listed in the Application Rates for Turfgrass Sites table. Apply using a minimum of 2 gals of water per 1,000 sq ft. Higher volumes (4 to 10 gals of water per 1,000 sq ft) may be needed for adequate coverage of dense turfgrass canopies and/or turfgrasses maintained under high mowing heights. Allow sufficient time for the application to dry before allowing pets or people to enter treatment area.		
Target insects must be exposed to the insecticide to be controlled. For optimum control of surface-feeding insects, delay irrigation or mowing for 24 hours after application. For subsurface-feeding insects, irrigate with 0.25 to 0.5 inch of water immediately after application.			
<b>NOTE: In New York State, product may not be applied to turf within 100 feet of a coastal marsh or stream that drains directly into a coastal marsh. For control of turf insects in New York, a second application may be made after two weeks if target insect activity persists.</b>			
<b>Application Rates For Turfgrass Sites:</b>			
	Sites	Pests	Rates
	Athletic fields, recreational areas, lawns & grounds, residential areas, parks, public and commercial sites	Ants, armyworms, centipedes, chiggers, cockroaches, crickets, cutworms, fleas(adult), grasshoppers, ground beetles, Japanese beetles (adults),	leafhoppers, mealybugs, pillbugs, scorpions, sod webworms, sowbugs, spring-tails, spiders, ticks
		Annual bluegrass weevil (adult), billbugs (adult), black turfgrass ataenius (adult),	chinch bugs, mites**, mole crickets
			0.4 to 0.6 fl oz/1,000 sq ft or 17.5 to 26 fl oz/A or 0.06 to 0.08 lb ai/A
Remarks			
Apply when pests become evident. Apply as a broadcast spray in a minimum of 2 gals of water per 1,000 sq ft Delay irrigation or mowing for 24 hours after application for optimum control of surface-feeders such as cutworms and webworms. For subsurface-feeders, such as mole crickets, irrigate with 0.25 to 0.5 inch of water immediately after application.			



**Landscape Ornamental Treatments**

Suspend SC Insecticide provides control of a wide range of insects on landscape ornamentals. Mix Suspend SC Insecticide with the required amount of water according to the Application Rates for Ornamentals table below. Thoroughly apply the finished spray to upper and lower leaf surfaces to ensure adequate coverage, but prior to dripping. Be sure to penetrate dense foliage to wet leaves, trunk and branches. Plant safety testing has been conducted on many species of ornamental plants under a wide range of environmental and cultural conditions and no injury has been observed. If local use information is not available, it is advisable to pre-spray a few plants.

**Application Rates for Ornamentals:**


Sites	Pests	Rates
Landscape ornamentals including trees, shrubs, evergreens and foliage plants	Adelgids, ants, aphids, azalea lace bugs, bagworms, boxelder bugs, cankerworms, cardamom thrips, cockroaches, crickets, elm leaf beetles, elm sawworms, European pine sawflies, fall webworms, flea beetles, flies, fungus gnats, grasshoppers, green-striped mapleworm, Gypsy moth (larvae), imported willow leaf beetles, Japanese beetles (adults)*, June beetles (adults), lace bugs, leaf-feeding caterpillars, leafhoppers, leaf	rollers, loopers, leaf skeletonizers, mealybugs, midges, mimosa webworms, mites**, orangestriped oakworms, pillbugs, pine shoot beetles, pine tip moths, pinyon spindle-gall midges, plant bugs, rehdumped caterpillar, red imported fire ants, sawfly larvae, sowbugs, spiders, springtails, spanworms, scale insects (crawlers), tent caterpillars, ticks, webworms, yellownecked caterpillar

4 to 8 fl oz/100 gals of water

**Remarks**

Apply when pests become evident. Thorough coverage is required for best results. Apply with sufficient water to ensure coverage of upper and lower leaf surfaces.

\* Will provide anti-feedant properties on treated ornamentals against Japanese beetles.  
 \*\*Suppression only.



## STORAGE AND DISPOSAL

Do not contaminate water, food, or feed by storage or disposal.

**STORAGE** Mix as needed. Store in original container in a secured dry storage area. Avoid extremes in temperatures. Prevent cross contamination with other pesticides and fertilizers. If the container is leaking and/or material is spilled on floor or paved surfaces, absorb on sawdust or other commercially available absorbing material, sweep up and remove to chemical waste area for your disposal. Concentrate is stable at normal storage temperatures.

**PESTICIDE DISPOSAL** Wastes resulting from the use of this product may be disposed of on site or at an approved waste disposal facility.

**CONTAINER HANDLING** [less than one gallon]  
 Nonrefillable container. Do not reuse or refill this container. Triple rinse container (or equivalent) promptly after emptying. Triple rinse as follows: Empty the remaining contents into application equipment or a mix tank and drain for 10 seconds after the flow begins to drip. Fill the container ¼ full with water and recap. Shake for 10 seconds. Pour rinsate into application equipment or a mix tank or store rinsate for later use or disposal. Drain for 10 seconds after the flow begins to drip. Repeat this procedure two more times. Securely wrap container in several layers of newspaper and discard in trash or offer for recycling if available. If partly filled: Call your local solid waste agency for disposal instructions. Never place unused product down any indoor or outdoor drain.


[One to 5 gallon size]  
 Nonrefillable container. Do not reuse or refill this container. Triple rinse container (or equivalent) promptly after emptying. Triple rinse as follows: Empty the remaining contents into application equipment or a mix tank and drain for 10 seconds after the flow begins to drip. Fill the container ¼ full with water and recap. Shake for 10 seconds. Pour rinsate into application equipment or a mix tank or store rinsate for later use or disposal. Drain for 10 seconds after the flow begins to drip. Repeat this procedure two more times. Offer for recycling or reconditioning, or puncture and dispose of in a sanitary landfill. If partly filled: Call your local solid waste agency for disposal instructions. Never place unused product down any indoor or outdoor drain.

### APPENDIX

Use this product as a general surface, spot, mist, or crack and crevice treatment. Permitted areas of use include the following buildings, structures, and modes of transport:

- aircraft (cargo holds only)
- apartment buildings
- bakeries
- bottling facilities
- breweries
- buses
- cafeterias
- candy plants
- cereal processing and manufacturing plants
- correctional facilities
- dairies and dairy product processing plants
- food manufacturing plants
- food processing plants
- food service establishments
- frozen food plants
- grain mills
- granaries
- greenhouses (structures only)
- hospitals
- hotels
- houses
- industrial buildings
- kitchens
- laboratories
- livestock housing
- pet kennels
- manufacturing establishments
- mausoleums
- meat, poultry & egg processing & packaging plants
- meat and produce canneries
- mobile & motor homes
- nursing homes
- offices
- pickle factories
- poultry houses
- processing and packing plants
- restaurants
- schools
- spice plants
- stores
- warehouses
- wineries and similar structures\*
- transportation vessels such as buses, trucks, trailers, rail cars, and marine vessels

*continued*



3.5"

5.5"

**APPENDIX (continued)**

For indoor applications at these sites, observe the following restrictions:

- Do not allow people or pets to contact treated areas until spray has dried.
- Do not apply in hospital and/or nursing home rooms while they are occupied.
- Do not apply in classrooms while they are occupied.
- Do not apply in aircraft cabins.
- Do not apply to furniture or upholstery where prolonged contact with humans will occur.
- Do not apply as a space spray.
- Do not allow excessive dripping or run-off to occur when treating vertical or overhead surfaces.
- Do not apply in conduits, motor housings, junction boxes, switch boxes, or other electrical equipment because of possible shock hazard.

For outdoor application at all listed sites:

- Do not apply Suspend SC Insecticide through any type of irrigation system.
- Do not apply this product to edible crops.

**IMPORTANT: READ BEFORE USE**

Read the entire Directions for Use, Conditions, Disclaimer of Warranties and Limitations of Liability before using this product. If terms are not acceptable, return the unopened product container at once.

By using this product, user or buyer accepts the following Conditions, Disclaimer of Warranties and Limitations of Liability.

**CONDITIONS:** The directions for use of this product are believed to be adequate and must be followed carefully. However, it is impossible to eliminate all risks associated with the use of this product. Crop injury, ineffectiveness or other unintended consequences may result because of such factors as weather conditions, presence of other materials, or the manner of use or application, all of which are beyond the control of Bayer CropScience LP. All such risks shall be assumed by the user or buyer.


**DISCLAIMER OF WARRANTIES:** TO THE EXTENT CONSISTENT WITH APPLICABLE LAW, BAYER CROPSCIENCE LP MAKES NO OTHER WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY OR OF FITNESS FOR A PARTICULAR PURPOSE OR OTHERWISE, THAT EXTEND BEYOND THE STATEMENTS MADE ON THIS LABEL. No agent of Bayer CropScience LP is authorized to make any warranties beyond those contained herein or to modify the warranties contained herein. TO THE EXTENT CONSISTENT WITH APPLICABLE LAW, BAYER CROPSCIENCE LP DISCLAIMS ANY LIABILITY WHATSOEVER FOR SPECIAL, INCIDENTAL OR CONSEQUENTIAL DAMAGES RESULTING FROM THE USE OR HANDLING OF THIS PRODUCT.

**LIMITATIONS OF LIABILITY:** TO THE EXTENT CONSISTENT WITH APPLICABLE LAW, THE EXCLUSIVE REMEDY OF THE USER OR BUYER FOR ANY AND ALL LOSSES, INJURIES OR DAMAGES RESULTING FROM THE USE OR HANDLING OF THIS PRODUCT, WHETHER IN CONTRACT, WARRANTY, TORT, NEGLIGENCE, STRICT LIABILITY OR OTHERWISE, SHALL NOT EXCEED THE PURCHASE PRICE PAID, OR AT BAYER CROPSCIENCE LP'S ELECTION, THE REPLACEMENT OF PRODUCT.

Bayer (reg'd), the Bayer Cross (reg'd) and Suspend® are registered trademarks of Bayer.

Produced for:  
Bayer Environmental Science  
A Division of Bayer CropScience LP  
5000 CentreGreen Way, Suite 400  
Cary, NC 27513







4"



# Suspend<sup>®</sup> SC

## INSECTICIDE

- \* For Residential, Industrial and Institutional Control of Major Nuisance Pests Listed on The Label
- \* Controls Numerous Pests in and around Households and Other Structures
- \* Will not Damage Paints, Plastics, Fabrics or Other Surfaces Where Water Alone Causes No Damage
- \* For Insect Control on Commercial and Residential Turf and Landscape Ornamental Plants

### ACTIVE INGREDIENTS:

\*Deltamethrin ..... 4.75%

OTHER INGREDIENTS: ..... 95.25%

TOTAL: ..... 100.00%

\*Contains 0.42 lb deltamethrin per gallon.

EPA Reg No. 432-763

## KEEP OUT OF REACH OF CHILDREN CAUTION

Si usted no entiende la etiqueta, busque a alguien para que se la explique a usted en detalle.

(If you do not understand the label, find someone to explain it to you in detail.)

FIRST AID	
If inhaled:	<ul style="list-style-type: none"> <li>• Move person to fresh air.</li> <li>• If person is not breathing, call 911 or an ambulance, then give artificial respiration, preferably by mouth-to-mouth, if possible.</li> <li>• Call a poison control center or doctor for further treatment advice.</li> </ul>
HOT LINE NUMBER	
Have the product container or label with you when calling a poison control center or doctor or going for treatment. You may also contact 1-800-334-7577 for emergency medical treatment.	

See Panel for First Aid Instructions and Booklet for Complete Precautionary Statements and Directions for Use.

## Net Contents 1 Gallon

85750720

85827804B 170421AV2

5.5"